



# Okaloosa County Airports

**Airport  
Project Title**

**Estimated Project Schedule**

---

---

Okaloosa Regional Airport

**ORA East Side Development**

**July 2008 – Dec 2008**

**Project Description:** Project consists of a new: Fuel Farm, Rental Car Facility, Car Wash, Fuel Stands, Cargo/Maintenance Facility, and parking.

**Advisories:** No passenger or flight impacts

**Weatherproof Movable Airport Boarding Units (MBU)**

**Oct 2007- Jun 2008**

**Project Description:** Project consists of the installation of 3 MBU's for use in the boarding and deplaning of passengers in a safe and efficient process.

**Advisories:** No passenger or flight impacts

**Okaloosa Regional Airport Master Plan Update**

**Nov 2007 – Nov 2008**

**Project Description:** Project consists of an Airport Master Plan update including an Airport Layout Plan. The Master Plan Update will develop an inventory of the current facilities, present forecasts of growth, assess the need for additional development, and provide a plan, including costs estimates, for additional development or rehabilitation. Recommendations will be made to ensure consistency with FAA Advisory Circulars and guidelines/ procedures.

**Advisories:** No passenger or flight impacts

**Okaloosa Regional Airport Terminal Additions Design Project**

**Jan 2008 – Dec 2008**

**Project Description:** With current and forecasted peak airport activities and the goal of attracting a "low cost" air carrier, the airport will expand to original design levels. Design consist of adding 3 to 4 gates on the south end of the concourse, expanding the east and west ends (ticketing and baggage claim), of the north end of the terminal and adding space for TSA. The estimated additions will increase the airports square footage by 50k. Estimated design schedule: 1 year.

**Advisories:** No passenger or flight impacts

**Remote Overnight Apron- Cargo Building Aircraft Parking Apron**

**Aug 2008 – Jan 2009**

**Project Description:** The project concept consists of the construction of a new approximately 8,500 square yard Portland cement concrete aircraft parking apron. The proposed apron will be approximately 300 feet by 250 feet sized to accommodate a B727 and B757 aircraft simultaneously.

**Advisories:** No passenger or flight impacts

## Bob Sikes Airport

### **West Hangar Area Infrastructure Expansion Phase III**

**May 2008 – Sep 2008**

**Project Description:** Project consists of completion of the original design for hangar development on the southwest side of Bob Sikes Airport. Construction includes ramp extension and utilities.

**Advisories:** Will be published as deemed necessary.

### **Interior build-out of the NOFD Airport Rescue & Fire Fighting Facility (ARFF)**

**May 2008 – Dec 2008**

**Project Description:** Build-out of interior improvements addressing approximately 8,000 sf of staff and support area and approximately 8,867 sf of truck parking/maintenance bays.

**Advisories:** Will be published as deemed necessary.

### **Bob Sikes Runway 17/35 Rehabilitation Phase II**

**Aug 2008 – Dec 2008**

**Project Description:** - Proposed project consists of remaining rehabilitation work on Runway 17-35. Phase 1 was completed December 07, which consisted of 4,425 LF of the 8,000 LF runway. Phase II consists of design bid services only for the remainder 3,575 LF. Rehabilitation consists of pavement strengthening, grade adjustments, safety area improvements, surface overlay, runway lighting and signage replacement and additional infrastructure considerations.

**Advisories:** Upon work commencement, NOTAMS will be filed for runway availability.

### **Bob Sikes Runway 17/35 Rehabilitation Phase I-A (Obstruction Removal)**

**June 2008 – Sep 2008**

**Project Description:** 12+ acres tree clearing, grubbing and sodding on the east side parallel to runway 17-35. Additional erosion control measure will be taken at the north end of the runway to protect the 1.3-acre conservation easement.

**Advisories:** Upon work commencement, NOTAMS will be filed for runway availability.

### **Bob Sikes Airport Master Plan Update**

**Nov 2007 – Jan 2009**

**Project Description:** Project consists of an Airport Master Plan update including an Airport Layout Plan. The Master Plan Update will develop an inventory of the current facilities, present forecasts of growth, assess the need for additional development, and provide a plan, including costs estimates, for additional development or rehabilitation. Recommendations will be made to ensure consistency with FAA Advisory Circulars and guidelines/ procedures.

**Advisories:** No passenger or flight impacts

## Ft. Walton Beach/ Destin Airport

### **Destin Master Plan Update**

**Nov 2007 – Jan 2009**

**Project Description:** Project consists of an Airport Master Plan update including an Airport Layout Plan. The Master Plan Update will develop an inventory of the current facilities, present forecasts of growth, assess the need for additional development, and provide a plan, including costs estimates, for additional development or rehabilitation. Recommendations will be made to ensure consistency with FAA Advisory Circulars and guidelines/ procedures.

**Advisories:** No passenger or flight impacts

### **Destin Airport Stormwater Master Plan**

**Suspended**

**Project Description:** Expansion projects are planned for the Destin-Ft. Walton Beach Airport in the future. Some are currently ongoing. Currently, any new developments are providing stormwater management on a piecemeal basis, thus serving only the specific development. The airport representatives would like to avoid the individual parcel approach, and develop a stormwater plan that accommodates and maximizes future expansion of the airport.

**Advisories:** No passenger or flight impacts

### **Destin/Ft. Walton Beach Airport Runway 14 & 32 PAPI Installation Systems**     **Aug 2008 – Dec 2008**

**Project Description:** Replacement of the 4-Box VASI system for Runway 14 and 32 with current driven 4-Box Precision Approach Path Indicator (PAPI) systems for both ends. The system will include 5KV cable in conduit, counterpoise and a constant current regulator in the airfield lighting vault.

**Advisories:** Upon work commencement, NOTAMS will be filed for runway availability.

### **Destin/Ft. Walton Airport Limited Site Assessment for Fuel Tank Area**

**Jun 2008 – Permanent**

**Project Description:** Soil investigation through borings and monitoring well installation and sampling.

**Advisories:** No passenger or flight impacts